



US Army Corps
of Engineers



TECHNICAL REPORT EL-88-15

NEW BEDFORD HARBOR SUPERFUND PROJECT, ACUSHNET RIVER ESTUARY ENGINEERING FEASIBILITY STUDY OF DREDGING AND DREDGED MATERIAL DISPOSAL ALTERNATIVES

Report 11

EVALUATION OF CONCEPTUAL DREDGING AND DISPOSAL ALTERNATIVES

by

Daniel E. Averett, Michael R. Palermo

Environmental Laboratory

DEPARTMENT OF THE ARMY

Waterways Experiment Station, Corps of Engineers
PO Box 631, Vicksburg, Mississippi 39181-0631

and

Mark J. Otis, Pamela B. Rubinoff

US Army Engineer Division, New England
Waltham, Massachusetts 02254-9149



July 1989

Report 11 of a Series

Approved For Public Release; Distribution Unlimited



Prepared for Environmental Protection Agency
Region 1, Boston, Massachusetts 02203-2211

REPORT DOCUMENTATION PAGE				Form Approved OMB No. 0704-0188	
1a. REPORT SECURITY CLASSIFICATION Unclassified			1b. RESTRICTIVE MARKINGS		
2a. SECURITY CLASSIFICATION AUTHORITY			3. DISTRIBUTION/AVAILABILITY OF REPORT Approved for public release; distribution unlimited.		
2b. DECLASSIFICATION/DOWNGRADING SCHEDULE					
4. PERFORMING ORGANIZATION REPORT NUMBER(S) Technical Report EL-88-15			5. MONITORING ORGANIZATION REPORT NUMBER(S)		
6a. NAME OF PERFORMING ORGANIZATION USAEWES, Environmental Laboratory; USAED, New England		6b. OFFICE SYMBOL (if applicable)	7a. NAME OF MONITORING ORGANIZATION		
6c. ADDRESS (City, State, and ZIP Code) PO Box 631, Vicksburg, MS 39181-0631; Waltham, MA 02254-9149			7b. ADDRESS (City, State, and ZIP Code)		
8a. NAME OF FUNDING/SPONSORING ORGANIZATION US Environmental Protection Agency, Region 1		8b. OFFICE SYMBOL (if applicable)	9. PROCUREMENT INSTRUMENT IDENTIFICATION NUMBER		
8c. ADDRESS (City, State, and ZIP Code) J. F. Kennedy Federal Building Boston, MA 02203-2211			10. SOURCE OF FUNDING NUMBERS		
			PROGRAM ELEMENT NO.	PROJECT NO.	TASK NO.
			WORK UNIT ACCESSION NO.		
11. TITLE (Include Security Classification) New Bedford Harbor Superfund Project, Achushnet River Estuary, Engineering Feasibility Study of Dredging and Dredged Material Disposal Alternatives; Report 11. Evaluation of Conceptual Dredging and Disposal Alternatives					
12. PERSONAL AUTHOR(S) Averett, Daniel E.; Palermo, Michael R.; Otis, Mark J.; Rubinoff, Pamela B.					
13a. TYPE OF REPORT Report 11 of a series		13b. TIME COVERED FROM Aug 85 to Jul 88	14. DATE OF REPORT (Year, Month, Day) July 1989		15. PAGE COUNT 245
16. SUPPLEMENTARY NOTATION Available from National Technical Information Service, 5285 Port Royal Road, Springfield, VA 22161.					
17. COSATI CODES			18. SUBJECT TERMS (Continue on reverse if necessary and identify by block number) See reverse.		
FIELD	GROUP	SUB-GROUP			
19. ABSTRACT (Continue on reverse if necessary and identify by block number) This report evaluates conceptual dredging and disposal alternatives for the Acushnet River Estuary, a part of the New Bedford Harbor Superfund Site. Dredging for removal of the highly contaminated sediment and subsequent disposal in upland or nearshore confined disposal facilities or disposal in contained aquatic disposal facilities are alternatives considered in the "Engineering Feasibility Study of Dredging and Dredged Material Disposal Alternatives." Sediment testing and sediment transport modeling performed as earlier tasks of the study form the basis for evaluation of the alternatives. The technical feasibility of conceptual design options is based on site availability, capacity, and characteristics and on sediment physical characteristics and dredged material settling behavior as defined by laboratory testing. Contaminant releases during dredging and disposal operations are estimated for each disposal option. A preliminary cost estimate for implementation of each option evaluated is also presented.					
20. DISTRIBUTION/AVAILABILITY OF ABSTRACT <input checked="" type="checkbox"/> UNCLASSIFIED/UNLIMITED <input type="checkbox"/> SAME AS RPT. <input type="checkbox"/> DTIC USERS			21. ABSTRACT SECURITY CLASSIFICATION Unclassified		
22a. NAME OF RESPONSIBLE INDIVIDUAL			22b. TELEPHONE (Include Area Code)		22c. OFFICE SYMBOL

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE

18. SUBJECT TERMS (Continued).

Confined disposal facility
Contained aquatic disposal
Contaminated sediment
Dredged material

Dredging
Feasibility study
Metals
New Bedford

Polychlorinated biphenyl
Remedial alternatives
Superfund

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE

PREFACE

This study was conducted as a part of the Acushnet River Estuary Engineering Feasibility Study (EFS) of Dredging and Dredged Material Disposal Alternatives. The US Army Corps of Engineers (USACE) performed the EFS for the US Environmental Protection Agency (USEPA), Region 1, as a component of the comprehensive USEPA Feasibility Study for the New Bedford Harbor Superfund Site, New Bedford, MA. This report, Report 11 of a series, was prepared by the US Army Engineer Waterways Experiment Station (WES) and the New England Division (NED), USACE. Coordination and management support was provided by the Omaha District, USACE, and dredging program coordination was provided by the Dredging Division, USACE. The study was conducted between August 1985 and July 1988.

Project manager for the USEPA was Mr. Frank Ciavattieri. The NED project managers were Messrs. Mark J. Otis and Alan Randall. Omaha District project managers were Messrs. Kevin Mayberry and William Bonneau. Project managers for the WES were Messrs. Norman R. Francingues, Jr., and Daniel E. Averett.

This report was prepared by Mr. Daniel E. Averett, Water Supply and Waste Treatment Group (WSWTG), Environmental Engineering Division (EED), Environmental Laboratory (EL), WES; Dr. Michael R. Palermo, Research Projects Group, EED; Mr. Mark J. Otis, New Bedford Superfund Project Office, Operations Division, NED; and Ms. Pamela B. Rubinoff, Coastal Engineering and Survey Section, Engineering Division, NED. Technical support in preparation of the report was provided by Mr. Bret Perry, WSWTG. The report was edited by Ms. Jessica S. Ruff of the WES Information Technology Laboratory.

This study was conducted under the general supervision of Mr. Norman R. Francingues, Jr., Chief, WSWTG; Dr. Raymond L. Montgomery, Chief, EED; Dr. John Harrison, Chief, EL; Mr. Vyto Andreliunas, NED; and Mr. David Mathis, Dredging Division, USACE.

COL Dwayne G. Lee, EN, was the Commander and Director of WES. Dr. Robert W. Whalin was Technical Director.

This report should be cited as follows:

Averett, Daniel E., Palermo, Michael R., Otis, Mark J., and Rubinoff, Pamela B. 1989. "New Bedford Harbor Superfund Project, Acushnet River Estuary Engineering Feasibility Study of Dredging and Dredged Material Disposal Alternatives; Report 11, Evaluation of Conceptual Dredging and Disposal Alternatives," Technical Report EL-88-15, US Army Engineer Waterways Experiment Station, Vicksburg, MS.

CONTENTS

PREFACE.....	1
CONVERSION FACTORS, NON-SI TO SI (METRIC) UNITS OF MEASUREMENT.....	5
PART I: INTRODUCTION.....	6
Background.....	7
Purpose and Scope.....	10
PART II: DESCRIPTION OF DISPOSAL OPTIONS.....	11
Upland Disposal.....	11
Nearshore Disposal.....	13
Contained Aquatic Disposal.....	15
PART III: REVIEW OF SEDIMENT CHARACTERISTICS AND REMOVAL OPTIONS.....	18
Depth and Area To Be Dredged.....	18
Sediment Characteristics.....	19
Dredging Equipment.....	21
PART IV: CONFINED DISPOSAL FACILITY EVALUATION.....	23
Background.....	23
Potential CDF Sites.....	24
Design Requirements.....	26
CDF Design Options.....	28
Control Technologies for CDF Options.....	32
Selection of CDF Design Option and Control Technology Schemes.....	38
Monitoring Requirements.....	39
PART V: CONTAINED AQUATIC DISPOSAL EVALUATION.....	40
Background.....	40
Purpose.....	41
Engineering Feasibility Determination.....	41
Criteria for Determining Implementability and Technical Effectiveness.....	42
Pilot Study.....	42
CAD Site Selection and Description.....	43
Selection of Capping Material.....	45
Equipment and Placement Techniques.....	45
Capping Thickness Requirements.....	47
Development of CAD Options.....	48
Sizing and Locating CAD Cells.....	50
Monitoring Requirements.....	56
Controls for CAD Options.....	57
PART VI: DETAILED ANALYSIS OF CDF AND CAD DESIGN OPTIONS.....	58
Evaluation Criteria.....	58
Detailed Evaluation.....	59
Summary.....	68
REFERENCES.....	69
TABLES 1-15	

FIGURES 1-42

APPENDIX A: TOPOGRAPHIC AND HYDROGRAPHIC SURVEY MAPS.....	A1
APPENDIX B: ENGINEERING CHARACTERIZATION OF SEDIMENTS FOR PURPOSES OF DREDGING AND DISPOSAL.....	B1
APPENDIX C: COST ESTIMATES FOR DREDGING AND DISPOSAL ALTERNATIVES.....	C1
APPENDIX D: ESTIMATED CONTAMINANT RELEASE FROM DREDGING AND DREDGED MATERIAL DISPOSAL.....	D1

CONVERSION FACTORS, NON-SI TO SI (METRIC)
UNITS OF MEASUREMENT

Non-SI units of measurement used in this report can be converted to SI (metric) units as follows:

<u>Multiply</u>	<u>By</u>	<u>To Obtain</u>
acres	4,046.873	square metres
cubic feet	0.02831685	cubic metres
cubic yards	0.7645549	cubic metres
feet	0.3048	metres
gallons (US liquid)	3.785412	cubic decimetres
horsepower (550 foot-pounds (force) per second)	745.6999	watts
inches	2.54	centimetres
miles (US nautical)	1.852	kilometres
pounds (mass)	0.4535924	kilograms
square feet	0.09290304	square metres
yards	0.9144	metres